

SHIP NAME

Mv Audacia



LOCATION Rotterdam, The Netherlands	CLASSIFICATION SOCIETY DNV
SHIP OWNER Allseas	TOTAL ORDER VALUE EUR 700,000.00
SHIPYARD Keppel Verolme	PIPE SYSTEMS Fibermar® & Wavistrong® systems
VESSEL TYPE Conversion Bulk Carrier – Pipe Laying vessel	PIPE SYSTEMS The Wavistrong® EST12 system included pipe & fittings. Diameter range from 100 mm up to 700 mm.
COMPLETION DATE 2007	

SCOPE

Major systems provided for this project included:

- Seawater cooling systems engine room I, II and forward equipment room

Our scope entailed a single point responsibility for the sea water cooling systems. FPI was fully responsible for all the activities required to produce a fully functional pipe system, including:

- Engineering: Preparation of Isometrics, bill of materials & spool drawings
- Manufacture of pipes and fittings
- Prefabrication of the spools
- Packing and delivery
- On-site installation

ADVANTAGES / SPECIAL ATTRIBUTES

Our understanding of the process involved helped us to ensure proper system design and the selection of most appropriate jointing system. Our site installation crew worked closely with the yard personnel to ensure proper installation of the pipes and fittings in a timely manner.