

**PROJECT**

Mobil "Zafiro Producer"



**CLIENT**

Mobil Equatorial Guinea

**OTHER PARTNERS**

23.75% Devon Energy, 5% Equatorial Guinea

**DETAILS**

Floating Production Unit (FPU)  
500feet (152meters) water depth  
VLCC Conversion

**PROJECT TEAM**

Mustang Engineering (Engineering)  
Dolphin Services (Shipyards)  
Delta Engineering (Shipyards)  
Oceaneering Production Systems (Project Mgmt)

**INSTALLATION**

Houma, LA and Channelview, TX USA (onshore)  
Block B, Equatorial Guinea (offshore Bioko Island)

**SYSTEMS SELECTED FOR FIBERBOND®:**

- Firewater, firewater deluge, seawater, chemical services
- 3,300feet (1,005meters) of piping, up to 24" (600NB)
- ABS-type approved products
- 200psig (13.8bar) design, 300psig (20.7bar) hydrotest

**FIBERBOND® SCOPE**

- Supply of materials
- Shop prefabrication
- Site installation including FRP welding
- Installation of supports, installation of flanges, and commissioning assistance

**HIGHLIGHTS**

- Installed warranty on entire system
- Operating since 1997